# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT19447/CALL-2

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016**

**Providing and Installing New motor pumps in ward no. 06 Byatarayanapura sub division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of P MOHAN RAJU | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 5 | Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 15.000 HP 25 stage (P.NO-XXXXIII, I.NO-33, PWD SR 13-14) 15 HP 30 Stage | No | 70496.46 | 352482.30 | Rupees Seventy Thousand Four Hundred Ninety Six and Forty Six Paise Only |
| 2 | 5 | 12.5 HP 25 Stage | No | 60290.26 | 301451.30 | Rupees Sixty Thousand Two Hundred Ninety and Twenty Six Paise Only |
| 3 | 440 | Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe (SR 13- | Rmtr | 339.3524 | 149315.06 | Rupees Three Hundred Thirty Nine and Thirty Five Paise Only |
| 4 | 500 | Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia (P.NO-535, I.NO-30 (c), BWSSB 12- | Mtr | 163.8518 | 81925.90 | Rupees One Hundred Sixty Three and Eighty Five Paise Only |
| 5 | 5 | Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR) | No. | 14760.52 | 73802.60 | Rupees Fourteen Thousand Seven Hundred Sixty and Fifty Two Paise Only |
| 6 | 110000 | Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14) | Sqm | 0.339093 | 37300.23 | and Thirty Three Paise Only |
| | | | | | 996277.39 | |

P. Mohan Raju

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

1/3/16